

SCOPE OF WORK FOR THE MOBILE UNITS TO BE SUPPLIED ON AN AS AND WHEN REQUIRED IN INLAND REGION

1.1 PLAN 1

- Mobile Offices, ablution and kitchen unit
- Insulated Open Plan office (3mx3m)
- 2x Windows with security bars
- Blinds in all windows should be fitted
- 1x Door (Exterior C deck)
- DB (Surface mounted) with earth leakage and should be a 220v
- 1xLight (5GL Fluorescent 1.2)
- 1x plug (5GL 16 AMP and 1 light switch)
- 4x Jacks (screw in)
- 4x slabs
- Vinyl floors
- 1x Step
- 1x air conditioning unit
- Security Hut
- 1x Office
- 18x Lockers

1.2 PLAN 3

- Mobile Offices, ablution and kitchen unit
- Insulated Open Plan office (3mx9.6m)
- 4x Windows with security bars and blinds in all windows
- 1x Door (Exterior C deck) and 1 x interior door
- DB (Surface mounted) with earth leakage and should be a 220v
- 4x Lights (5GL Fluorescent 1.2)
- 4x plugs (5GL 16 AMP and 2 light switches)
- 6x Jacks (screw in)
- 6x slabs
- Vinyl floors
- 1x Step
- 2x air conditioning units
- 4x Offices
- 56x Lockers

1.3 PLAN 5

- Mobile Offices, ablution and kitchen unit
- Insulated Open Plan office (3mx12m)
- 5x Windows with security bars and blinds in all windows
- 2x Doors (Exterior C deck)
- DB (Surface mounted) with earth leakage and should be a 220v
- 4x Lights (5GL Fluorescent 1.2)
- 4x plugs (5GL 16 AMP and 2 light switches)
- 6x Jacks (screw in)

- 6x slabs
- Vinyl floors
- 1x Step
- 2x air conditioning units
- 4x Offices
- 60x Lockers
- 2x Security Hut

1.4 PLAN 8

- Mobile Offices, ablution and kitchen unit
- Insulated Open Plan office (3mx12m) offices and lockers
- 5x Windows with security bars and blinds in all windows
- 3x Doors (Exterior C deck) and 2x interior doors
- DB (Surface mounted) with earth leakage and should be a 220v
- 3x Lights (5GL Fluorescent 1.2)
- 4x plugs (5GL 16 AMP and 3 light switches)
- 6x Jacks (screw in)
- 6x slabs
- Vinyl floors
- 3x Steps
- 3x air conditioning units
- 3x Offices
- 60x Lockers

1.5 PLAN 9

- Mobile Offices, ablution and kitchen unit
- Insulated Open Plan office (3mx6m) offices
- 2x Windows with security bars and blinds in all windows
- 2x Doors (Exterior C deck) and 1x interior door
- DB (Surface mounted) with earth leakage and should be a 220v
- 2x Lights (5GL Fluorescent 1.2)
- 2x plugs
- (5GL 16 AMP and 2 light switches)
- 4x Jacks (screw in)
- 4x slabs
- Vinyl floors
- 2x Steps
- 2x air conditioning units
- 2x Offices
- 40x Lockers

1.6 PLAN 12

- Mobile Offices, ablution and kitchen unit
- Insulated Open Plan office (2.3mx3m) shower and toilet
- 2x Windows with security bars and blinds in all windows
- 2x Doors (Exterior C deck) and 2x interior doors
- 1x Water proof DB with earth leakage and should be a 220v

- 2x Lights (Bowl fittings)
- 2 light switches
- 4x Jacks (screw in)
- 4x slabs
- Vinyl floors
- 2x Steps
- Plumbing (2x wash hand basins and 1x waste closet)
- 1x shower
- 1x urinal
- 1x 50lt geyser
- Male showers and Female shower for 7 to 10 people

1.7 PLAN 13

- Mobile Offices, ablution and kitchen unit
- Insulated Open Plan office (2.3mx3m) male and female toilets
- 2x Windows with security bars and blinds in all windows
- 2x Doors (Exterior C deck) and 2x interior doors
- 1x Waterproof DB with earth leakage and should be a 220v
- 2x Lights (Bowl fittings)
- 2 light switches
- 4x Jacks (screw in)
- 4x slabs
- Vinyl floors
- 2x Steps
- Plumbing (2x wash hand basins and 2x waste closets)
- 1x urinal
- Female and male toilets for 14 to 20 people

1.8 PLAN 14

- Mobile Offices, ablution and kitchen unit
- Insulated Open Plan office (2.3mx6m) showers and toilets for males and females
- 3x Windows with security bars and blinds in all windows
- 1x Door (Exterior C deck) and 3x shower doors
- 2x Waterproof DB with earth leakage and should be a 220v
- 2x Lights (Bowl fittings)
- 1 light switch
- 4x Jacks (screw in)
- 4x slabs
- Vinyl floors
- 1x Step
- Plumbing (3x wash hand basins and 3x waste closets)
- 3x Showers
- 2x urinals
- 200lt geyser
- Female and male toilets for 21 to 30 people

1.9 PLAN 21

- Mobile Offices, ablution and kitchen unit
- Insulated Open Plan office (2.3mx6m) showers and toilets for males and females
- 3x Windows with security bars and blinds in all windows
- 2x Door (Exterior C deck) – one for office and one for the toilet
- 2x Waterproof DB with earth leakage and should be a 220v
- 2x Lights (1x Fluorescent, 1x Bowl fitting)
- 1 light switch
- 4x Jacks (screw in)
- 4x slabs
- Vinyl floors
- 2x Steps
- Plumbing (1x wash hand basin and 1x toilet)
- 1x Shower
- 200lt geyser