

SCOPE OF WORK FOR THE MOBILE UNITS TO BE SUPPLIED AS AND WHEN REQUIRED IN THE INLAND REGION AND SURROUNDING AREAS

1.1 PLAN 1

- Mobile Offices, ablution and kitchen unit
- Insulated Open Plan office (3mx3m)
- 2x Windows with security bars and blinds in all windows
- 1x Door (Exterior C deck)
- DB (Surface mounted) with earth leakage and should be a 220v
- 1x Light (5GL Fluorescent 1.2)
- 1x plugs (5GL 16 AMP and 1 light switch)
- 4x Jacks (screw in)
- 4x slabs
- Vinyl floors
- 1x Step

1.2 PLAN 2

- Mobile Offices, ablution and kitchen unit
- Insulated Open Plan office (3mx9.6m)
- 4x Windows with security bars and blinds in all windows
- 1x Door (Exterior C deck)
- DB (Surface mounted) with earth leakage and should be a 220v
- 3x Lights (5GL Fluorescent 1.2)
- 4x plugs (5GL 16 AMP and 1 light switch)
- 6x Jacks (screw in)
- 6x slabs
- Vinyl floors
- 1x Step
- 2x air conditioning units

1.3 PLAN 3

- Mobile Offices, ablution and kitchen unit
- Insulated (3mx9.6m) mobile unit (2 offices, 3mx4.8m each)
- 4x Windows with security bars and blinds in all windows
- 1x Door (Exterior C deck) and 1 x interior door
- DB (Surface mounted) with earth leakage and should be a 220v
- 4x Lights (5GL Fluorescent 1.2)
- 4x plugs (5GL 16 AMP and 2 light switches)
- 6x Jacks (screw in)
- 6x slabs
- Vinyl floors
- 1x Step
- 2x air conditioning units

1.4 **PLAN 5**

- Mobile Offices, ablution and kitchen unit
- Insulated Open Plan office (3mx12m)
- 5x Windows with security bars and blinds in all windows
- 2x Doors (Exterior C deck)
- DB (Surface mounted) with earth leakage and should be a 220v
- 4x Lights (5GL Fluorescent 1.2)
- 4x plugs (5GL 16 AMP and 2 light switches)
- 6x Jacks (screw in)
- 6x slabs
- Vinyl floors
- 1x Step
- 2x air conditioning units

1.5 **PLAN 6**

- Mobile Offices, ablution and kitchen unit
- Insulated Open Plan office (3mx6m)
- 2x Windows with security bars and blinds in all windows
- 1x Door (Exterior C deck)
- DB (Surface mounted) with earth leakage and should be a 220v
- 2x Lights (5GL Fluorescent 1.2)
- 3x plugs (5GL 16 AMP and 1 light switch)
- 4x Jacks (screw in)
- 4x slabs
- Vinyl floors
- 1x Step
- 1x air conditioning unit

1.6 **PLAN 8**

- Mobile Offices, ablution and kitchen unit
- Insulated (3mx12m) mobile unit (3 offices, 4mx3m each)
- 5x Windows with security bars and blinds in all windows
- 3x Doors (Exterior C deck) and 2x interior doors
- DB (Surface mounted) with earth leakage and should be a 220v
- 3x Lights (5GL Fluorescent 1.2)
- 4x plugs (5GL 16 AMP and 3 light switches)
- 6x Jacks (screw in)
- 6x slabs
- Vinyl floors
- 3x Steps
- 3x air conditioning units

1.7 **PLAN 9**

- Mobile Offices, ablution and kitchen unit
- Insulated (3mx6m) mobile unit (2 offices, 3mx3m each)
- 2x Windows with security bars and blinds in all windows
- 2x Doors (Exterior C deck) and 1x interior door
- DB (Surface mounted) with earth leakage and should be a 220v
- 2x Lights (5GL Fluorescent 1.2)
- 2x plugs (5GL 16 AMP and 2 light switches)
- 4x Jacks (screw in)
- 4x slabs
- Vinyl floors
- 2x Steps
- 2x air conditioning units

1.8 **PLAN 10**

- Mobile Offices, ablution and kitchen unit
- Insulated (3mx12m) mobile unit (4 offices, 3mx3m each)
- 4x Windows with security bars and blinds in all windows
- 4x Doors (Exterior C deck)
- DB (Surface mounted) with earth leakage and should be a 220v
- 4x Lights (5GL Fluorescent 1.2)
- 4 x plugs (5GL 16 AMP and 4 light switches)
- 6x Jacks (screw in)
- 6x slabs
- Vinyl floors
- 4x Steps
- 4x air conditioning units

1.9 **PLAN 12**

- Mobile Offices, ablution and kitchen unit
- Insulated (2.3mx3m) shower and toilet
- 2x Windows with security bars and blinds in all windows
- 2x Doors (Exterior C deck) and 2x interior doors
- 1x Waterproof DB with earth leakage and should be a 220v
- 2x Lights (Bowl fittings)
- 2 light switches
- 4x Jacks (screw in)
- 4x slabs
- Vinyl floors
- 2x Steps
- Plumbing (2x wash hand basins and 1x waste closet)
- 1x shower
- 1x urinal
- 1x 50lt geyser

1.10 **PLAN 13**

- Mobile Offices, ablution and kitchen unit
- Insulated (2.3mx3m) male or female toilets
- 2x Windows with security bars and blinds in all windows
- 2x Doors (Exterior C deck) and 2x interior doors
- 1x Waterproof DB with earth leakage and should be a 220v
- 2x Lights (Bowl fittings)
- 2 light switches
- 4x Jacks (screw in)
- 4x slabs
- Vinyl floors
- 2x Steps
- Plumbing (2x wash hand basins and 2x waste closets)
- 1x urinal

1.11 **PLAN 14**

- Mobile Offices, ablution and kitchen unit
- Insulated (2.3mx6m) showers and toilets for males or females
- 3x Windows with security bars and blinds in all windows
- 1x Door (Exterior C deck) and 3x interior doors and 3x shower doors
- 2x Waterproof DB with earth leakage and should be a 220v
- 2x Lights (Bowl fittings)
- 1 light switch
- 4x Jacks (screw in)
- 4x slabs
- Vinyl floors
- 1x Step
- Plumbing (3x wash hand basins and 3x waste closets)
- 3x Showers
- 2x urinals
- 200lt geyser

1.12 **PLAN 22**

- Mobile Offices, ablution and kitchen unit
- Insulated (2.3mx6m) office with toilet
- 3x Windows with security bars and blinds in all windows
- 2x Doors (Exterior C deck)
- DB (Surface mounted) with earth leakage and should be a 220v
- 2x Lights (1x Bowl fittings and 1x 5GL Fluorescent 1.2)
- 2x plugs (5GL 16 AMP and 1 light switch)
- 4x Jacks (screw in)
- 4x slabs
- Vinyl floors
- 2x Steps
- Plumbing (1x wash hand basin and 1x waste closet)
- 1x Shower
- 1X geyser

1.13 **NEW PLAN**

- Mobile Offices, ablution and kitchen unit
- Insulated (3mx9.4m) toilets
- 9x Windows with security bars and blinds in all windows
- 2x Doors (Exterior C deck) and 11x interior doors
- 1x Waterproof DB with earth leakage and should be a 220v
- 4x Lights (Bowl fittings)
- 2x light switches
- 6x Jacks (screw in)
- 6x slabs
- Vinyl floors
- 2x Steps
- Plumbing (7x wash hand basin and 12x waste closet)
- 4x Urinal
- 150lt geyser

Note: Quantities for other Park Home requirements will be communicated during the execution of the project, as and when the need arises.