

17 September 2026

CLARIFICATION 01

TNPA/2026/08/0003/114698/RFP – THE MAINTENANCE OF BUILDING AND MARINE DEPOT IN THE PORT OF DURBAN FOR A PERIOD OF SIX (6) MONTHS

QUESTION	ANSWER
1.The following information remains outstanding: - Referenced tender drawings. - Door and window schedules. - Specifications and required thicknesses for the F50 self-levelling screed and epoxy flooring under BoQ items 1.3, 3.4 and 6.11. - Concrete repair specification for BoQ item 4.4. - Clarification of crack repair measurement under BoQ item 2.12. - Confirmation of the Industrial Relations Practitioner staffing requirements	Clarification is as follows: - The drawings are attached. - The doors and windows schedule are not available, however the descriptions (material and sizes) are provided on the pricing schedule. - F50 self levelling screed thickness should be 15mm laid on Bondite primer, then the epoxy floor coat should be 10mm slip resistance shop floor. - Concrete repair method: - Square cut the edge of identified repairs to a minimum depth of 10mm to avoid further edging. - Remove all unsound concrete including concrete within the square cut and ensure concrete behind the reinforcement is broken/ chipped back enough to allow access of priming a steel a minimum of 25mm is recommended. - The exposed reinforced steel must be sand blasted to remove all rust. - Apply double coat of zinc primer to reinforcing steel. - Apply wet to dry epoxy adhesive to the

Transnet SOC Ltd
Registration Number
1990/000900/30

eMendi Building
N2 Neptune Road
Off Klub Road
Port of Ngqura
Port Elizabeth
6100

P.O. Box 1159
Port Elizabeth
South Africa
6000

Non-Executive Directors: TP Nchocho (Chairperson), K Phihela, V Dube, S Lund, C Benjamin
M Abdool* (Chief Executive), T Mpileleli* (Chief Financial Officer)
*Executive

TNPA Company Secretary: Mr NS Selepe

www.transnet.net

"This letterhead contains personal information as defined in the **Protection of Personal Information Act, No. 4 of 2013** (the "Act"). The signatory consents to the processing of his/ her personal information and is obliged to handle other data subject's information in accordance with the requirements of the Act".

	prepared concrete surface. - Apply structural repair mortar and smooth over on the exterior face. • The correct unit of measurement for cracks is linear metres, amendment will be made. With reference to clauses 6.7.4–6.7.6 of the Works Information (PDF page 134), the duties mentioned may also be undertaken by a suitably qualified member of the contractor's existing site management team.
2. We request for an extension of the tender closing date, from 22 September 2026 to 9 October 2026 at 14h00.	2. Please see Addendum 01 but extended until 29 September 2026 at 14h00.
3. What type of experience is required on 4. Stage Three: Technical Eligibility?	3. Only certificates are required for this stage of evaluation.



17/09/2026



17.09.2026