

QUESTION & ANSWER SHEET NUMBER 3 – FOR THE PROVISION OF SERVICES TO UPGRADE THE EXISTING TRANSNET NATIONAL PORTS AUTHORITY (TNPA) NATIONAL FIRE SERVICE INFRASTRUCTURE AND EQUIPMENT PROJECT (PHASE 2A) IN THE PORT OF CAPE TOWN FOR A PERIOD OF 1 (ONE) YEAR.

Q1	can you please clarify item 35 on page 53 of pricing data.
A1	The correct measurement is 1.6m, Please see addendum number 2.
Q2	The roofing supplier responded that the BOQ and specifications do not match up. Please advise.
A2	<p>Changed to "Locally produced 0,58mm thick 700mm cover concealed fix 700™ profile " Dark Dolphin" finish top coat and backing coat Aluminium roof sheeting, fixed to 50 x 76 new timber purlins fixed to 114 x 38mm Grade 5 new SA pine roof trusses with 3.0 deg slope, all in accordance with the manufacturer`s specifications".</p> <p>Please see addendum number 2- Bill No.12: Roof Preambles - Item No.2</p>
Q3	<p>Please can you provide more detail/specifications for the road signs, the suppliers do not know what road signs to quote on.</p> <p>It does not show which type of signs are involved. It only gives the specifications regarding the Chromadek plate and Sign face material.</p> <p>If the units was changed to sq/m and not No. then I could possible price it as such which would then cover most types of signs.</p> <p>There is also no provision for supports.</p>
A3	Road signs have been removed from the bill of quantities