CLARIFICATION FEEDBACK REGISTER:					
RFP NUMBER: iCLM EL 725/TPT					
REFURBISHMENT OF THE GRAIN ELEVATOR SUBSTATIONS AT THE EAST LONDON MULTI PURPOSE TERMINAL FOR TRANSNET SOC LTD (REG NO. 1990/000900/30) OPERATING AS TRANSNET PORT TERMINALS (HEREINAFTER REFERRED AS "TPT") FOR THE DURATION OF 12 MONTHS					
NUMBER	**REFERENCE**	**DATE RECEIVED**	**CLARIFICATION REQUIRED/QUERY/REQUEST**	**TPT RESPONSE DATE**	**TPT RESPONSE**
1	Scope of Works - Clause 7.5 (e) & (f)	21/11/2024	Whilst we acknowledge the Scope of Works as per clause 7.5 (e) and (f) and can make the necessary allowances for the Earthing requirements in the Substations, we're concerned about the lightning Surge Protection requirements as this could mean reviewing the entire Terminal Building Lightning Protection Installation & making good.	22/11/2024	For an external lightning protection system, bidders shall make an allowance for 4 interconnected air termination rods with down conductors from four corners of the building and earth terminations. This shall be for the building. For the internal protection system, the bidders shall consider sufficient, as if there is none, surge protection and equipotential bonding only for the concerned substation/s rooms.