



## DURBAN RORO MPT TERMINAL

Document Title:

# SCOPE OF WORK

Project Title:

**Hiring of TWO (2 x Reach Stackers) Machines  
for RORO MPT TERMINAL (POINT).**

**REVISION 01: REQUEST FOR QUOTATION**

### 1 SCOPE OF WORK

#### 1. General Description of the Work

The work consists of **hiring of 2 (two) Reach Stackers** Equipment's at Durban RORO Terminal, for a **period of THREE months** contracted to 500 hours PER MACHINE per month. **(Five Hundreds Hours per Reach Stacker Per Month)**

#### 1.1 Technical Specification

- Self-propelled Telescopic boom lift, diesel engine.
- 45T-50T capacity
- 6000-8000MM Wheelbase.
- 9300-15100mm maximum lifting height
- Anti-collision Technology of the Spreaders while Revolving
- Fire extinguisher not expired
- Operational Revolving light
- Operational Reverse buzzer

#### 1.2 Requirements from the Supplier

- Supplier must provide equipment maintenance as per OEM requirements
- Call out response for breakdown repairs with their own labour and provide a spare machine in the interim to support technical in an event of an extended breakdown.
- response time must be within ONE hours from the time of notification
- Successful bidders will be required submit a safety file which will be verified by TPTs SHERQ department for compliance.
- Provide valid load test certificates for all machines
- All specification on clause 1.1 and 1.2 must be met and the overall condition of machinery must be good.

2. Inspection must be done by TPT Roro Terminal Technical examiner on the delivery date and will be accepted when examiner have approved it and certified fit for duty.

3. Please ensure equipment is delivered before 13:00 preferable in morning for inspection to be conducted and load test certificate must come with the machinery is to be performed daily at workshop wash bay which includes but not limited to:

**NB: Any deviation from the scope needs to be authorised before the work is performed.**

TRANSNET PORT TERMINALS	Scope of Work for Hiring of 2 Reach Stackers Equipment			DURBAN RORO TERMINAL
			Page 3	