

<b>Item No.</b>	<b>Description</b>	<b>Unit</b>	<b>QTY</b>	<b>Rate per unit - ZAR , Excl VAT</b>	<b>Total - ZAR , Excl VAT</b>	<b>Comments</b>
1	Provision of Health and Safety File	Sum	1			
2	Site preparation and civil works	Sum	1			Includes bund walls and slabs
3	Supply and installation of 2 x 20,000L JoJo tanks	Each	2			With fittings and connections
4	Supply and installation of 2000L oil storage tank	Each	1			Plastic tank
5	Provision of New Skimming System	Sum	1			Stainless Steel for wet components
6	Supply and install stainless steel oil separator	Sum	1			Complete with accessories
7	Install totalization flow meters (sewer & effluent)	Each	2			
8	Supply and installation of effluent pump	Each	1			Same size as existing
9	Automatic level sensors & transfer motor	Set	1			Includes PLC connection
10	Shade roof with subframes	Sum	1			Over JoJo tank area
11	Industrial DB board (metal, orange)	Each	1			Fully labelled with surge protection
12	System automation and PLC integration	Sum	1			Includes mobile/PC monitoring

13	Horn/siren notification system	Each	1			Connected to fault detection system
14	Remote alarm & mobile notification system	Sum	1			With user configuration
15	Lighting installation around the plant	Sum	1			LED , 200W
16	Supply and installation of ClearVu fence	m	70			2.4m high with anti-climb design
17	Pedestrian access gate	Each	2			Lockable, same finish as fence
18	Plant Roofing Structure, Steel Sheets (Cover the entire effluent plant) – Galvanized Steel, IBR Sheets	M2	460			To extend beyond the fencing and divert rainwater to surrounding area beyond the effluent Plant – To include all structural posts and Plinths required (Gap Between Fencing and Roof should not be sufficient for an individual to gain access)
19	Supply and Installation of Security Detection System	Sum	1			As per specification
20	Supply and Installation of Agitation system as per specification	Sum	1			

21	Design drawings and documentation	Sum	1			Includes all schematics and manuals
22	System commissioning & testing	Sum	1			Includes commissioning report
23	Training of staff	Sessions	1			Includes operational SOPs
				Total (Excl VAT)		
				VAT @ 15%		
				Total (incl VAT)		

Name: Sibonelo Msizazwe  
Designation: Project Manager

Date 04 June 2025

Name: Qaasim Soeker  
Designation: Plant Engineer

Date 03.06.2025