



PRICING SCHEDULE REQUIREMENTS

Tenderer (Company)	Responsible Person	Designation	Date
Project/Tender Title	Project/Tender No.	Project Location / Description	
Environmental Monitoring Service, at the Bulk Terminal RO Plant Port of Saldanha on a weekly and monthly basis for a period of - three (3) months		Transnet Port Terminals, Saldanha for the Iron Ore Terminal	

The following is the minimum list of pricing items that must be submitted to the Contract Manager by the contractor for approval

ITEM NO.	DESCRIPTION OF SERVICE	QUANTITY FOR 3 MONTHS	RATE PER MONTH [ZAR]	TOTAL RATE FOR 3 MONTHS
1	Measurement of pH, temperature, salinity, dissolved oxygen concentration and saturation, in the brine basin of the RO Plant and at weekly intervals.	3		
2	Collection and analysis of a composite brine samples for analysis of trace metals Chromium, Nickel, Iron, Manganese (Cr, Ni, Fe, Mn), and Total Suspended Solids (TSS), salinity, Ph and toxicity (using a test such as the sea urchin fertilisation test) at monthly intervals in the brine basin and effluent drain leading to municipal drainage system.	3		
3	Collection of water samples from the middle and bottom of the water column at three stations situated 50 m from each point of discharge and analysis for salinity, pH, turbidity, total suspended solids, metals (Fe, As, Cd, Cu, Cr, Hg, Mn, Ni, Pb, Zn), and toxicity (using a test such as the sea urchin fertilisation test) every 3 months/ Quarterly .	1		
8	Deliver a detailed quarterly presentation listing the following: The extract volume discharge, showing daily, weekly and monthly discharge volumes; Incidents that have occurred during emergency, malfunction or upset conditions; The result/ findings or the monitoring requirements in terms of the permit and where further monitoring is required.	1		
TOTAL PRICE, exclusive of VAT:				R
VAT 15% (if applicable)				R
Discount(s)				R
Total Inclusive of VAT (where applicable)				R